CHITALDRUG DIVISION.

The 25th May 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 10th June 1898, for the construction of a new building for the Anglo-Vernacular School at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 7 & 11 A. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the construction of a new building for the Anglo-Vernacular School at Davangere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Details of work.	*Per.*	*Quantity.*
Earthwork excavation	C. yd.	432
Concrete	C. ft.	2,818
Burnt brick in chunam	"	22,864
Archwork do	"	167
Chunam plastering	Sqrs.	216·23
White and colour washing	"	216·23
Flooring with Cuddapah slab stones over 3" concrete and cement pointing.	"	42·79
Cornice work (Dental)	R. ft.	480
Coping	"	176
Stone pillars (7½' high)	No.	18
Teakwood work	C. ft.	551·06
Roofing with 1st class Mangalore tiles, teakwood reepers, screw, &c., complete, including ridging.	Sqrs.	69·36
Teakwood doors	S. ft.	1,050
Teakwood windows including iron bars and glass shutters inside.	"	693
Teakwood ventilators including frames and glass shutters, &c., complete.	"	278
Mouldings	R. ft.	152
Eave boards (Teakwood)	"	120
Finials (Teakwood)	Each.	8
Burnt stone slabs 6" thick dressed	S. ft.	1,183
Wood oiling to wood work	Sqrs.	65·01
Chocolate painting to doors, windows, eave boards, &c. ..	"	39·75
Sun shades	Each.	24
Levelling ground	L. S.	..
Hedge round the compound	"	..

K. PRAHLADA RAO, *Exec. Engineer.*

BANGALORE CITY MUNICIPALITY.

TENDERS FOR LIGHTING STREET LAMPS.

Notice, dated 14th May 1898.

Sealed tenders will be received by the undersigned up to 2 P. M. on Monday the 27th June next for lighting with kerosine-oil Silber-burners all road and street lamps within the Municipal limits of the City of Bangalore for a period of one year commencing from the 1st August 1898.